

Date: Monday, 1/30/2006 8:08:29 AM  
 User: Kim Johnston

## Process Sheet

Customer	: CU-DAR001 Dart Helicopters Services	Drawing Name	: PLUG
Job Number	: 25655		
Estimate Number	: 10930		
P.O. Number	: N/A	Part Number	: D2057
This Issue	: 1/30/2006 S.O. No. : N/A	Drawing Number	: D2057 REV B
Prsht Rev.	: NC	Project Number	: N/A
First Issue	: N/A Type : MACHINED PARTS	Drawing Revision	: B
Previous Run	: N/A	Material	: N/A
Written By	: <u>SEE COMMENT BELOW</u>	Due Date	: 2/20/2006
Checked & Approved By	: <u>06.01.30</u>	Qty:	100 Um: Each
Comment	: Est D 02.08.22 Make in Cobra KJ		

## Additional Product

Job Number:



Seq. #:	Machine Or Operation:	Description :
---------	-----------------------	---------------

1.0	M6061T6R0750	6061-T6 Round Bar .750"
-----	--------------	-------------------------



Comment: Qty.: 0.1050 f(s)/Unit Total : 10.5000 f(s)  
 6061-T6 Round Bar .750"  
 Material: 6061-T6 (QQ-A-225/8) Ø0.75 Rod  
 (M6061T6R0.750) Batch M19430

ml 06/02/06

2.0	HARDINGE	HARDINGE CNC LATHE SMALL
-----	----------	--------------------------



Comment: HARDINGE CNC LATHE SMALL  
 Make as per Dwg D2057 and Folio FA260.  
 Break all sharp edges 0.015 max. Do not drill Ø0.191

3.0	-QC6 QC2	DIMENSIONAL CHECK
-----	----------	-------------------



Comment: DIMENSIONAL CHECK

BG 06.02.07 100

4.0	PACKAGING 1	PACKAGING RESOURCE #1
-----	-------------	-----------------------



Comment: PACKAGING RESOURCE #1  
 Identify and Stock  
 Location: STU19

06/2/8 (100)

5.0	DC	DOCUMENT CONTROL
-----	----	------------------



Comment: DOCUMENT CONTROL  
 Inspection Level 21

SUR 06/02/09 (100)

06/02/09

Job Completion



# Dart Aerospace Ltd

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: LD Date: 06/02/09  
 QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_


NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries



DESIGN	JB	DRAWN BY	<i>JP</i>	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED	<i>DAH</i>	APPROVED	<i>KE</i>	DRAWING NO. D2057	REV. B SHEET 1 OF 1
DATE	98.10.15			TITLE PLUG	SCALE 2:1
A	92.03.13			NEW ISSUE	
B	98.10.15			REDRAWN 0.191 DIA WAS 0.187 DIA (TSR A1100)	

RELEASED  
98.10.16 DS



SHOP COPY  
RETURN TO  
ENGINEERING  
UNCONTROLLED COPY  
SUBJECT TO AMENDMENT  
WITHOUT NOTICE  
WORK ORDER  
NO. 25655

MATERIAL: 6061-T6 ROD (QQ-A-225/8)  
FINISH: NONE  
BREAK ALL SHARP EDGES 0.015 MAX  
TOLERANCES PER DART QSI 018 UNLESS OTHERWISE NOTED

